



DETAIL NOTES:

- FURNISHED BY DOYON UTILITIES, INSTALLED BY ELECTRICAL CONTRACTOR. LEAVE REMAINING LENGTH COILED AT ONE END. DO NOT CUT TO FIT.
- FURNISHED BY DOYON UTILITIES, INSTALLED BY ELECTRICAL CONTRACTOR. PANEL TO BE MOUNTED A MINIMUM OF 36" A.F.F.
- FURNISHED BY DOYON UTILITIES, INSTALLED BY ELECTRICAL CONTRACTOR.
- EXACT LOCATION OF THE BUILDING INTERFACE CONTROL PANEL SHALL BE ITERATIVELY DETERMINED (IE., TEST, RELOCATE IF NECESSARY, RETEST), AS THE POINT AT WHICH RECEPTION BY THE TANTALUS ELECTRIC METER IS OPTIMALLY ACHIEVED. IF FINAL LOCATION IS NOT ACCEPTABLE TO THE ENGINEER, TRANSMITTERS CAN BE REMOTE MOUNTED FROM THE PANEL.

DEVICE TAGS						
BUILDING CODE	BUILDING NAME	BUILDING METER INTERFACE PANEL	STEAM METER	WATER METER	PUMP	UTILITIES MONITORING CONTROL PANEL
336A	AIRCRAFT PARTS STORAGE	CP-336AM	FIT-336A-MPS	FT-336A-DCW	NONE	CP-G693

DETAIL 1 BUILDING METER INTERFACE

N.I.S.

PC-05

REV. NO.	DATE	DESCRIPTION
0	05/09/11	RECORD DRAWING

FOSDICK & HILMER 309 VINE STREET, SUITE 50 TELEPHONE (513)241-5640	CONSULTING ENGINEERS CINCINNATI, OHIO 45202 WWW.FHEVG.COM	Jimmy Huntington Building 714 Fourth Avenue, Suite 20 Fairbanks, Alaska 99701 Telephone (907) 455-1500 Fax (907) 455-6788	Date: 04/09/10 Scale: NTS Designed By: J.T. Drawn By: G.N. Checked By: J.T.	UTILITY SERVICE EXTENSION TO AIRCRAFT PARTS STORAGE BUILDING METER INTERFACE DETAIL	Fort Wainwright, AK. DU PROJECT NO. J101395, 101396, 101397	Drawing No. PC-06
--	---	---	---	--	--	----------------------